



3D Technology Solutions in Construction

Verification of Retaining Wall System

TEAM Conference Branson, MO March 14, 2024

Gregory Cleveland, PE, CCM SAM







Table of contents







What is 3D Technology Solutions for Construction?

- In general, 3D technology enhances a traditional 2D view or model to provide a more realistic view
- 3D software and 3D scanning are helping to improve safety, productivity and quality during construction phase operations
- Key Benefits of 3D Construction:
 - Conceptually view project features in the field
 - Compare as-built versus as-designed
 - Make insightful decisions timely
 - Improve construction quality




SA//

Establishing TxDOT Pilot Projects



- TxDOT is embracing Digital Delivery
 - 3D plans using Bentley's OpenRoads Designer
 - Machine models for construction
- Created 3D Construction Inspection Pilot Projects
- Goals:
 - Evaluate readily available 3D technology
 - Compare as-built versus as-designed
 - Evaluate precision and accuracy
 - Assess ease of use








Establishing TxDOT Pilot Projects



- I-2/I-69C Design-Build Interchange (\$303M)
 - TxDOT Pharr District
 - 4 DC's and associated roadways
 - Pilot: May 2023
- Southeast Connector Design-Build (\$1.6B)
 - TxDOT Fort Worth District
 - Widening of I-20, I-820, US 287
 - Pilot: August 2023





- Technical Working Group (TWG) Established
 - Weekly meetings at first; moving to bi-weekly
 - Coordination/communication between TxDOT Districts and Divisions (ALD/CST), DB Contractor, Surveyors, and Vendors
 - Preconstruction, Construction, Post-Construction phases
- Trimble SiteVision Visualization tool using mixed reality and ORD plans
- Bentley Synchro
 — Inspection forms tied to element and P6 schedule






- Preconstruction Phase Tasks
 - Equipment delivery/setup/training takes time to learn
 - ORD file transfer to Trimble Connect requires ORD experience
 - Equipment site calibration
 - Compared project survey control well within 0.1 foot
 - Be aware of obstructions
 - Survey experience required



Trimble SiteVision User Guide




Site Calibrations with SAM and DB Contractor Surveyors





- Preconstruction Phase Tasks
 - Retaining Wall 2-33 & 2-35
 - Review bridge plans and retaining wall shop drawings
 - Measurements to the back of proposed retaining wall panels from the drilled shaft extensions






- Construction Phase Tasks
 - Verify leveling pad layout
 - Measuring tape was used to verify Trimble measurements
 - Pulled tape from the edge of the drilled shaft to the proposed back of panel
 - Trimble depicts leveling pad is at the right location










- Construction Phase Tasks
 - Verify placement of panel
 - Plan dimension is 2.75' (2'-9")
 - Trimble measurement is 2.74'
 - The placement of the panel is acceptable






SA//

- Construction Phase Tasks
 - Verify elevation of leveling pad
 - Plans elevation = 107.78'
 - Trimble elevation = 107.83'
 - Leveling pad is 0.05' above plan elevation
 - Elevation of leveling pad is considered acceptable



SA//

- Construction Phase Tasks
 - Review Edge of Roadway Profile
 - Prior to paving operations
 - GNSS measurements performed
 - Interface between coping and hot-mix pavement
 - Comparison made to elevations from as-designed cross-sections







Benchmark # 2 Actual Elevation = 110.01' GNSS Elevation = 110.00'

Benchmark # 3 Actual Elevation = 108.61' GNSS Elevation = 108.62'









- Construction Phase Tasks
 - Edge of Roadway Profile Review
 - Actual profile is 0.23' or 2.76" lower than as-designed
 - Critical Hold Point Inspections
 - Elevation of leveling pad
 - Tolerances between panels
 - Coping level up concrete





-			
Station	As-Built Coping Elev., FT	As-Designed Edge of Roadway Elev., FT	As-Built to As-Designed Delta, FT
1513+80	133.96	134.14	-0.18
1514+00	133.62	133.89	-0.27
1514+50	133.17	133.49	-0.32
1515+00	132.85	133.10	-0.25
1515+50	132.31	132.6	-0.29
1516+00	131.81	132.01	-0.20
1516+50	131.14	131.32	-0.18
1517+00	130.32	130.50	-0.18
1517+50	129.34	129.53	-0.19
		Average>	-0.23





- Equipment used viDoc RTK Rover, iPad Pro and the Pix4D application
- Obtained localization file from DB Contractor and scanned benchmarks to verify calibration of equipment
- Calibration was an issue and worked with Vendor to resolve
- Scans of retaining wall features to verify prior to panel placements













- Construction Phase Tasks
 - Verify levelness of leveling pad
 - Spec: no more than 1" plastic shim height is used
 - Scan performed and measured
 - Slope = 0.2%
 - Elevation difference = 0.39" < 1"
 - Leveling pad is considered level





- Construction Phase Tasks
 - Verify slope direction of subgrade
 - Line was drawn between top of leveling pad toward the underdrain area
 - Elevation difference = 0.57'
 - Subgrade is sloping correctly










- Construction Phase Tasks
 - Verify underdrain is lower than subgrade
 - Measured using point feature with elevation difference = 1.24' lower



 Pix4D also takes hundreds of geotagged photos while scanning
















Bentley Synchro (Efforts to date)



- Bentley Suite of software include many packages
- To support 3D Construction Inspection, the pilot project focused on two key aspects
 - Form Building Technology
 - Dashboard Functionality
- Proof of concept
 - Develop Construction Inspection forms
 - Use Dashboards to present key project metrics


SYNCHRO The construction solution SYNCHRO Construction Web Mobile Cloud				
SYNCHRO Field		SYNCHRO Perform New	SYNCHRO Cost New	SYNCHRO 4D
Mobile field management Tablet and phone workflows For	Project management Task- & model-based workflows For	Project performance Optimised site operations For	Cost management Project- & portfolio-level costs For	Plan & virtual construc Model-authoring & workflow For
Field Staff including • Superintendents • Foremen • Field Engineers' • Inspectors	Project Admins including Project Managers Project Directors Doc Controllers Safety & Quality Managers	Site Managers including • Superintendents • Foremen • Project Managers • Safety & Quality Managers	Cost Managers including • Bid Mgrs – Biz Dev • Estimators • Cost Managers • Project Managers	Planners & VDC Mgrs includit Planners/Schedulers Estimators VDC Engineers Project Managers
who need to quickly capture and access data in the field	who need to better manage all docs, data and tasks in one place	who want real-time access to field performance to keep projects in control	To more easily manage contracts and project budget in order to better manage risk and cash flow	that optimize resources and deliver projects on time and budget
WWW.BENTLEY.COM © 2022 Bentley Syste	ms, Incorporated			Ben



- Construction Inspection Forms
 - <u>Core features</u>: date, location, weather, schedule, element of work, specification requirements, observations, photos
 - <u>Enhancements</u>: conforming/non-conforming work, P6 schedule, % complete, safety, environmental, record keeping, tied to other work (e.g., testing)

Item Series	Item	Item Description	Section	Reference	Requirement
400	416	DRILLED SHAFT FOUNDATIONS	Materials	Safety	Has proper protection been placed around drilling site?
400	416	DRILLED SHAFT FOUNDATIONS	Materials	416.2	Concrete mixture design is approved for installation
400	416	DRILLED SHAFT FOUNDATIONS	Materials	416.2	Approved water-reducing admixture is used when using casing that will be
400	416	DRILLED SHAFT FOUNDATIONS	Materials	416.2	Does mineal drilling slurry meet Table 3 requirements?
400	416	DRILLED SHAFT FOUNDATIONS	Materials	416.2	Slurry testing performed, if applicable
400	416	DRILLED SHAFT FOUNDATIONS	Materials	Record Keeping	Tag for the reinforcing steel
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	General Notes	Casing is required for 18" Drilled Shafts
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Drilled Shaft Installation Plan Submittal and Review are completed
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Drilled Shaft location tolerances:
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Vertical plumbness is 1in. per 10ft. of depth
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Center of shaft located under column is within 1in. of horizontal plan positi
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Center of shaft located inder footing is within 3in. of horizontal plan position
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Has embankment at bridge ends been installed prior to installing drilled sh
400	416	DRILLED SHAFT FOUNDATIONS	CONSTRUCTION	416.3	Do drilled shafts passing through the structural volume of retaining walls m
400	416	DRILLED SHAFT FOUNDATIONS	DRY DRILLING	416.3.1	Shaft has been excavated through all anticipated materials encountered to
400	416	DRILLED SHAFT FOUNDATIONS	DRY DRILLING	416.3.1	Was satisfactory found material encountered at the plan elevation?
400	416	DRILLED SHAFT FOUNDATIONS	DRY DRILLING	416.3.1	If not, has engineer approved any adjustments made to the bottom of shaf
400	416	DRILLED SHAFT FOUNDATIONS	DRY DRILLING	416.3.1	Has there been any caving condition, ground water seepage, or soil squeez
400	416	DRILLED SHAFT FOUNDATIONS	SLURRY DISPLACEMENT METHOD	Environmental	Are measures in place to contain slurry runoff?
400	416	DRILLED SHAFT FOUNDATIONS	SLURRY DISPLACEMENT METHOD	416.3.4	Was slurry mixed on-site in a reservoir of sufficient capacity, and allowed t
400	416	DRILLED SHAFT FOUNDATIONS	SUURRY DISPLACEMENT METHOD	416.3.4	Was a head of slurry maintained at or near ground level during and after ex








Bentley Synchro (Efforts to date)



- Construction Inspection Forms
 - Using Synchro Form builder
 - Creating OV and IQF inspection forms for:
 - Item 416, Drilled Shafts
 - Item 423, Retaining Walls
 - Not duplicating efforts with CST
 - Adding form enhancements



Bentley Synchro (Efforts to date)



- Synchro Dashboard Development
 - Dashboards created using metadata from inspection forms
 - Examples will include:
 - Approved Inspection Reports
 - NCRs/CDRs trending over time
 - Draw Request by Work and Activity ID

Draw Request Information

12/14/2022 12:00 AM

09/08/2022 12:00 AM 05/18/2023 12:00 AM 05/25/2023 12:00 AM


ent netadata	$\begin{array}{c c c c c c c c c c c c c c c c c c c $	Anton Teaching Anton Ant	CRS Trending over Time		
	Inspections by Element of Work	wei weiterer weiterer weiterer weiterer 20 weiter weiterer weiterer weiterer 15 10 5 5 6 15 0 5 6 16 5 0 5 17 5 0 5	Oct Nov Dec Jan 2023 File Mar	Apr May Jun	Jul Aug
ne	PM: Platwork Ut Utilie PA: Pavement De Deninge st. Egra on 17 (0.5%) CE Concreto (8.5%) To Concreto (8.5%) To Technological Project Schedule	s: 40 (148%) 120 (443%) 153 (6.65%) 14 Markings:	dge 1494 (55.2%)		
ctivity ID	Work Date	Schedule Activity ID	✓ Activity Name ✓	Scheduled Start Date 🗸 🗸	Scheduled End Date 🗸
	View 08/28/2023	03:59 PM RD08915	Embankment - (089/90)	11/3/2023 08:00	11/28/2023 16:00
Estimated % Complete 🗸 🛛 Schedule Activit	View 08/28/2023	01:46 PM BR1120154	Drill Shafts (Bent) - BR112-01	3/30/2023 08:00	5/25/2023 16:00
25 BR1080650	View 08/28/2023 Bridge 108 B	01:44 PM BR1120259	Drill Shafts (Bent) - BR112-02	4/4/2023 08:00	5/25/2023 16:00
100 BR1042517	View 08/28/2023 DS-96-3520	01:40 PM BR1111237	Drill Shafts (Bent) - BR111-12	5/18/2023 08:00	5/19/2023 16:00
20 TSS2	View 08/28/2023 F-SHAPE BAR	10:36 AM RW-S2A-21A-1	ERW-CN1-608 (RW-S2A-21A) - 058 - P1	5/22/2023 08:00	6/15/2023 16:00
20 TSS2	View 08/28/2023	10:10 AM RD07818	Rdwy Finishing (Perm Rail/Barrier/Etc) (078.1)	1/9/2026 08:00	1/29/2026 16:00
25 RD1170	PERMANENT ROAD WIDENING EXCAVATION				
100 BR1080647	R108 bent 6 cap				

SAM Applied Technology Group



- SAM is the largest combined geospatial solutions and inspection services provider in the nation
- SAM Applied Technologies (AT) Group consists of Software Programmers, Surveyors, & Engineers
- Key Services:
 - Application Design and Implementation
 - Security and GIS Website Deployment Services
 - Mobile Application Development
 - Custom Programming and Workflow Design





Retaining Wall Construction










Retaining Wall Construction







Next Steps



- I-2/I-69C (retaining wall, DC-1, UAS)
- SEC Connector (TWG, columns/drainage, other technology)
- Approval for proof-of-concept forms and dashboard
- Possible long-term activities:
 - Merge LiDAR scans into Bentley ORD to document progress
 - Develop Quick Reference Guides (QRG)
 - District Training Materials
 - Develop testing forms
 - Tie inspection, testing, progress, and payment to Element of Work



Questions & Answers





Gregory Cleveland, PE, CCM Director of Construction Services gcleveland@sam-cs.biz 214-403-7064



Ryan Burch, PE Construction Manager Ryan.Burch@sam-cs.biz 512-694-0898



Adam Long, PE, PS, RPLS Chief Technology Officer <u>ALong@sam.biz</u> 512-685-3548



Amanda Jenkins Accredited Premier Scholar Bentley OpenRoads Designer Amanda.Jenkins@sam.biz 512-647-8922



