EMERGENCY BRIDGE REPAIRS

A look at Emergency Repairs due to Critical Findings and Truck Impacts in Missouri, Illinois and Kansas

Scott Moeder, PE & Ryan Hagerty, PE



Emergency Project Spotlights

Purpose:

To highlight the amount of emergency repair projects that happen on a regular basis due to truck impacts and critical findings.



Common Themes for Emergency Repair Projects

 Schedule is insane, DOTs are looking at PS&E plans in a matter of weeks.

- Constant communication between the DOT & consultant is key to timely decisions.
- A bridge will always get hit at the most inopportune time.

Be very clear in explaining unique lump sum items




KDOT SB I-35 over SW Blvd

Kansas City, Kansas













BA

KDOT Mission Road Barrier Hit

Leawood, Kansas









KDOT College Blvd. Wall Failure

Leawood, Kansas
















Br No 15 101 237 05 (023)

10 18 17

Chin



TYPICAL SECTION - OVERHANG & PARAPET REMOVAL (On Bridge) (Looking South)



7 Rehab. plans)

Notes:


A 12 inch strip of Bridge Deck Overlay shall be removed to a clean line in areas of Parapet Only Removal.


Follow saw cut depth recommendations provided to avoid damage to reinforcing steel. Depth dimensions are from top of overlay or face of concrete. Adjust saw cut depth if reinforcing steel is encountered.

REMOVAL OF EXISTING BRIDGE STRUCTURES: Take care not to damage existing reinforcing steel in the overhang and parapet, clean and reuse, unless damaged or section loss is found.

Existing concrete surface to be covered by new concrete shall kness and Overlay be thoroughly roughened and cleaned prior to placing new concrete.

Note: Dimensions taken from rehab 1987 plans.







TUDIO IL FUICTINO OUFDIIANO CEOTION









MoDOT Route MM over I-44



It's usually a matter of inches

















Br. No. 196-8-28.38 (160) 8-18-17 Chip 8-2-10 Girder A, left side, 8-16-17 impact, 2 exposed strands, (none were severed).





Br. No. 196-8-28.38 (160) 8-18-17 Girder A, left side, 2015 impact, (hit again in 2017).

Chip 8-2-11




PARTIAL SECTION

NOTE: Existing Beam Concrete: f'c = 5,000 p.s.i.




US-75 over Topeka Blvd. Topeka, KS
















MoDOT Route 370 over Ferguson Lane St. Louis County, MO















SUGGESTED SEQUENCE OF CONSTRUCTION


- 1. Mark layout lines on bridge deck as follows:
- a. Mark layout lines representing € Bents 2 and 3. Mark transverse saw cut lines AA and BB at limits of removal near Bents 2 and 3. See Part Plan Limits of Removal.
- b. Mark longitudinal saw cut lines 1. 2. and 3 as shown in Part Plan Limits of Removal.
- c. Mark transverse and skewed saw cut lines at precast slab panel joint locations. Contractor to field verify and modify accordingly.
- Saw 1" deep out on each face of concrete barrier at AA and BB. Carefully remove barrier concrete at east and west limits to preserve longitudinal reinforcing steel.
- 3. Provide 9" deep saw outs at longitudinal line 1.
- Remove cast-in-place bridge deck overhang from fascia longitudinal cut line 1. This will include the removal of slab drains.

5a. Saw cut bridge deck as follows and per Part Plan - Limits of Removal:

- a. 9" deep saw cuts at longitudinal line 2.
- b. 2" deep saw cut at longitudinal line 3.
- c. 2" deep saw cuts at transverse lines AA and BB.
- d. 5% deep saw cuts at transverse and skewed precast panel joint locations.
- 5b. Remove cast-in-place deck and precast slab panels between longitudinal lines 1 and 2 as shown in Part Plan Limits of Removal.
- 6. Saw 1" deep cut in each face of Bents 2 and 3 diaphragms located 5'-3g" from % of Girder 14 as shown on Sheet No. 3.

- 7. Carefully remove Bents 2 and 3 diaphragms to limits shown in Elevation and Sections B-B and C-C on Sheet No. 3 using handheld chipping harmers as specified in Sec 704.4.1.2. Care shall be taken to preserve the longitudinal deak reinforcing steel near Bents 2 and 3 for installation of mechanical bar splices. When removing concrete between the ends of girders at Bents 2 and 3 care shall be taken so as to not damage the prestressing strands protruding from the ends of Girder 14. Span 1 and Girder 14. Span 3.
- Remove steel intermediate diaphragm and store for future re-installation.
- Remove Girder 14. Span 2. Remove and dispose of existing bearing devices and joint filler at Bents 2 and 3.
- 10. Carefully remove concrete deck at Girder 13 to limits shown in Section A-A using lightweight handheld chipping harmers. State of the section of the sect
- 11. Install bearing devices and joint filler at Bents 2 and 3.
- Set replacement Girder 14 and reinstall steel intermediate diaphragm.
- 13. Install precast slab panels.
- 14. Form deck and diaphragms. Install mechanical bar splices, deck reinforcing steel, diaphragm reinforcing steel, and slob drains. Partially install barrier curb reinforcing steel embedded within deck.
- 15. Place diaphragm and bridge deck concrete. Cure in accordance with Sec 703.3.6.
- 16. Install remaining barrier curb reinforcing steel. Place barrier curb concrete.
- 17. Install sign brackets and sign on slab.





DETAIL "A

SECTION B-B (Similar at out line BB)

PALPARES CLOSE NO 401

MO

SHEET IN 2

J6M0283

A48961

architects

engineers

16305 Swingley Ridge Rd. Sulfa 300 Chesterflett, MO 63017 6 3 6 2 4 0 2 4 4 4 www.gbateam.com


OEGROE BUTLER
ASSOCIATES INC.
PRO. ENGINEER GOOTS!
ARCHITECT GOOTS
BO. LAND SURVETOR GOO

RYAN G. HAGERTY PROFESSIONAL

DEMOLITION PLAN

























K-39 Bridge over Lone Star Haul Road:

- NW corner of Chanute
- Just West of US-169









• Slab bridge with a 2 column pier 1 column pier








- Column concrete completely broken
- More than half of column steel broken





100 Ton Rock Truck

- 150,000 lb empty weight
- 350,000 lb loaded weight
- F250 and 6' step ladder for scale...





- Damage to truck…
- Toy version is less than \$50 on ebay...









Project Schedule:

- 1/14/21 Bridge Hit
- 1/15/21 KDOT contacts GBA
- 1/15/21 Field visit with KDOT
- 1/22/21 Conceptual plan due (delivered 1/19/21)
- 1/25/21 90% Plans to KDOT
- 1/29/21 Final Plans for bid
- 2/5/21 Contract Awarded (with completion deadline 3/31/21)



Putting it back together:

- Pavement removal
- Excavated for new footing
- Temporary soil nail wall
- Pour new footing
- H-pile struts with jacks
- Straighten/couple rebar
- Pour new column







Lift the bridge back to original profile before pouring the new column







K-39 was closed during construction. This caused problems for other projects...






MoDOT Route J/NN over Route 60 Springfield, MO








Notes:

Design Force is the factored shear force at any cross section in the limits of FRP wrap that shall be resisted entirely by the FRP Reinforcement.

See special provisions.



PART ELEVATION AT DAMAGED LOCATION OF GIRDER NO. 2 IN SPAN (1-2)

Payment for all repairs and incidentals to the prestressed girder damage locations, complete in place, will be considered completely covered by the contract unit prices for Superstructure Repair (Unformed). Epoxy Pressure Injecting, and Fiber Reinforced Polymer Wrap.

Extreme care shall be taken when chipping to sound concrete and saw cutting of the prestressed girders as to not damage any prestressed strands or stirrups.


Live load not allowed on Girder No. 2 in Spans (1-2) & (2-3) during damage repairs.

ELEVATION OF GIRDER NO. 2 IN SPAN (1-2) (Looking West)


-Epoxy Inject Cracks Existing FRP Wrap Stirrups-Provisions) (Typ.) Existing Prestressing Saw Cut Strands -1/2" Deep Chip to Sound Concrete & Apply Epoxy Bonding Agent (Typ.) -Superstructure Saw Cut Repair (Unformed) 1/2" Deep-(Typ.)(See Sec 704) Bend existing stirrup back into place - Approximate Limits of

SECTION A-A

*3/8°0 x 3 1/2° threaded concrete lag screws at 6° max Imum grld spacing (minimum of 3 screws) within the maximum grio spacing (minimum of 3 screws) within the limits of spalled/damaged concrete. Screws shall be embedded a minimum of 2° into sound wall panel, have a minimum clearance of 11/2° to edges of panel, have a minimum clearance of 1" to each face of panel, be painted with protective coating, and be approved by the engineer prior to installation. The cost of all work associated with the installation of lag screws shall be completely covered by the contract unit price for Substructure Repair (Unformed).



SECTION B-B



PART ELEVATION AT DAMAGED

Payment for all repairs and incidentals to the MSE wall damage locations, complete in place, will be considered completely covered by the contract unit prices for Substructure Repair (Unformed) and Epoxy Pressure Injecting.

LOCATION OF MSE WALL A83521

DUSTIN TREGNAGO PROFESTONAL ENGINEER PE-2016012977

GBP

980t Renner Blvd. Sts. 200 Leneva, KS 662'B

913.492.0400

GBAteam.com

GEORGE BUTLER

ASSOCIATES, INC. PRO, ENGINEER 000133

ARCHITECT DOGS12

RD. LAND SURVEYOR COORS

PLANS

NOT APPROVED

FOR

CONSTRUCTION

11/3/2023 MO

A83031

60 BR GREENE JSUM0050 CONTRACT ID.

DETAILS OF CONCRETE I-GIRDER AND MSE WALL REPAIR

Spalled/Damaged Concrete

Schedule

Incident occurred on 10/6/2023

GBA contacted on 10/9/2023

NTP received on 10/11/2023

Final PS&E 11/07/2023

Advertised to contractors on 11/9/2023

 Had intermittent submittals to the District to allow expedited review time.



IDOT Overhead Sign Impact LaSalle, IL











MoDOT Overhead Sign Impact St. Louis, MO







Thank you for Listening. Questions?

